

# Major Projects Community Update

## Projects Completed/Underway in the 3rd Quarter

Bargo Streetscape



Spring Creek Rd Reconstruction



Lisa Rd Reconstruction



Garbutt PI Resurfacing





## Projects Completed/Under Way in the 3rd Quarter

**Shire Library Renovation** - 75% of electrical, hydraulic and mechanical services and internal fit-out work is complete. In April the internal lift and awning steel structure will be installed.

**Bargo Streetscape** - Concrete works, kerb & gutter, planter boxes and street furniture installation for the first three stages is complete. The final stage of construction work will resume in early April.

**Garbutt Pl, Oakdale** - During January the road was milled using a profiler, spray sealed to waterproof the pavement and then resurfaced with asphaltic concrete.

**Bollard Pl, Picton** - To minimise disruption to businesses, reconstruction of the culdesac was carried out over two nights in late January.

**Lisa Rd, Wilton** - Heavy patching works were carried out in December and road reconstruction was completed in February.

**Spring Creek Rd** - Following drainage works and heavy patching in December, road reconstruction of a 300 metre section was carried out in March.

**Silverdale Rd, Big Hill Rd to Garlicks Range Rd** - Preparation for road reconstruction was in full swing in March, with works scheduled to begin at Orangeville in early April.

**Remembrance Dwy, Cawdor** - Night works were carried out during March due to the very high traffic volume in the area, involving extensive asphaltic concreting. A spray seal for this stretch of road is scheduled for later in 2016.

**Whipbird Rd, Pheasants Nest** - Maintenance works and construction of a turning bay was carried out in March.

**Bargo Sportsfield Maintenance Shed Upgrade** - Minor upgrade works on five buildings (AFL Change Room, small Amenities Room, Tennis Club House, Scout Hall and Trotting Tower) at Bargo Sportsground are complete.

**Remembrance Dwy, Myrtle Creek Shared Footpath** - Design is now complete and the existing spray seal pathway will be reconstructed using concrete during April, with 50% of funding provided by Roads and Maritime Services (RMS).

**Regreme Rd, Picton** - Roundabout design is complete and relocation of services is under way with construction scheduled to begin in April.

**Bargo Sportsground Drainage** - Drainage work is due to commence in early April. The existing irrigation system will be capped off where needed, followed by installation of new irrigation (at a lower depth) with risers for the sprinkler heads and placement of the sprinklers.

**Wilton Sportsground** - Council is currently working with a consultant to prepare a draft Wilton Recreation Reserve Master Plan which will be placed on public exhibition over the coming months. Construction is expected to start in the new Financial Year.

**Picton Sportsground Bridge** - The bridge is currently out to tender with a report expected to go to the May Council Meeting. Construction will follow later in the year.



Whipbird Rd



Library Restoration



Bollard Pl Resurfacing



Bargo Streetscape Bus Stop

Projects Completed	Completed
<b>ROADS</b>	
Oaks St, Thirlmere Pedestrian Crossing - Upgrade	July
Camden Rd, Douglas Park - Road reconstruction	August
Tahmoor Accessible Parking Spot - Modification including signage and ramp	August
Broughton Pass Signage Project - New load limit signage	September
East St Couridjah - Sealing of unsealed road	October
Menangle Rd, Menangle - Road reconstruction	October
Skarrats Lane, Lakesland - Sealing of unsealed road	November
Remembrance Dwy south of Bargo River Bridge - RMS funded road reconstruction	November
Montpelier Dr (near the dairy) - RMS funded road reconstruction	November
Castlereagh St, Tahmoor - Kerb & gutter construction	November
Old Oaks Rd, The Oaks - Sealing of unsealed road	December
Garbutt Place, Oakdale - Heavy patching / road resurfacing with asphaltic concrete	January
Bollard Pl, Picton (Bridge St to Culdesac)	January
Lisa Rd, Wilton - Road reconstruction	February
Spring Creek Road, Mt Hunter - Heavy patching, drainage and road reconstruction	March
Whipbird Rd, Pheasants Nest - Maintenance & construction of turning bay	March
Remembrance Dwy, Cawdor - Asphaltic concrete works from Finns Rd to Bridgewater	March
<b>FACILITIES</b>	
Picton School of Arts - New roof sheeting	July
Colden St Temporary Library Renovation - Temporary Library now operating	August
Bargo Sportsfield Maintenance Shed Upgrade	March
<b>Projects Under Way</b>	<b>Progress</b>
<b>ROADS</b>	
Bargo Streetscape - Drainage, K&G Noongah St (complete), works recommencing April	Commenced October
Regreme Rd - Roundabout design and service relocation	Commenced January
Silverdale Rd, Big Hill Rd to Garlicks Range Rd - Road Reconstruction	Commenced March
Remembrance Dwy, Myrtle Creek - Footpath	Design/set out in March
Wilton Rd/Broughton Pass - RMS Funded Road Reconstruction	Contractor engaged for April
<b>FACILITIES</b>	
Shire Library Renovation - Internal strip-out complete, services being installed	Commenced September
Bargo RFS Station - DA lodged, contamination & geotechnical testing completed	Commenced July
Bargo Playing Field Drainage	Preparing to start on site in April
Wilton Sportsground - Design & construction	Design commenced March
Picton Sportsground - Bridge and linkages commencement	Tender closing April

Projects Scheduled	Scheduled for...
<b>ROADS</b>	
<b>Bridge St, Picton</b> (Argyle St to West of Rail Bridge) - Road Reconstruction	4th Quarter
<b>Estonian Rd/Oaks Rd</b> - RMS Funded Road Reconstruction	4th Quarter
<b>Rapleys Loop Rd</b> - Sealing of Unsealed Rd	4th Quarter
<b>Moorland Rd, Tahmoor</b> - Kerb & Gutter Stage 1	4th Quarter
<b>Margaret St/Argyle St Signals</b>	2016-17 Financial Year
<b>Fairleys Rd, Picton</b> - Road Reconstruction	2016-17 Financial Year
<b>Caloola Rd, Bargo</b> - Sealing of Unsealed Rd	2016-17 Financial Year
<b>Argyle St, Prince St To Connellan</b> - Road Widening	2016-17 Financial Year
<b>Remembrance Dwy Razorback</b> - Rockfall Site	To be Confirmed
<b>Kennedy St Appin Cycleway</b>	To be Confirmed
<b>Almond St/Picton Rd intersection</b> - Design (With Infrastructure Planning)	To be Confirmed
<b>Quarry Rd, The Oaks</b> - Replace Bridge with Piped Culvert	To be Confirmed
<b>FACILITIES</b>	
<b>Antill Golf Club</b> - Fire Safety	4th Quarter
<b>Appin Playing Field</b> - Drainage	4th Quarter



Remembrance Dwy, Cawdor