Plant List				
ID	Qty	Common Name	Botanical Name	Scheduled Size
Trees				
AlLi	31	Black She Oak	Allocasuarina littoralis	5 litre
Cal sal	184	Willow Botlebrush	Callistemon salignus	5 litre

Callistemon salignus

Allocasuarina torulosa

PROPOSED ROW OF WILLOW BOTTLEBRUSH AT 2.5m CENTRES, PLANTED IN MULCHED TRENCH,2m INSIDE BOUNDARY FENCE, WITH DRIP IRRIGATION

184-Callistemon salignus

Existing Dam

PROPOSED ROW OF BLACK SHE-OAK AT 2.5m CENTRES IN MULCHED PLANTING TRENCH WITH DRIP IRRIGATION

31-Allocasuarina littoralis

PROPOSED MAINTAINED GRASS BANK

PROPOSED MARKET GARDEN

PROPOSED DAM

Existing fenceline

Existing grassland

New fenceline

Kurrajong tree to be removed (400Dia 7H 7S approx location)

ASHWOOD ROAD

PROPOSED MAINTAINED GRASS AREA

LOT 542
DP 559948

Existing Kurrajong trees retained

Grassed Absorption Trench

Existing shed and fences to be removed

Existing Privett hedge to be removed (environmental weed)

Existing orchard trees in poor condition - to be removed where necessary

PROPOSED MARKET GARDEN

PROPOSED MARKET GARDEN

Cumberland Plain Shale Sandstone Transition Forest

Existing vehicle circulation space

Cabin

Existing Shed

PP

PP

PP

Existing gravel access road

2 dead conifer to be removed

Eucalyptus crebra to be removed (600dia 8H6S approx location)

Row of existing Pinus radiata

Existing Eucalyptus crebra retained

Existing Eucalypt (Grey gum) to be retained

Shed

Shed



SCREEN PLANTING - EXCAVATE TRENCH MINIMUM 300 WIDE AND 300 DEEP. BACKFILL WITH TOPSOIL/ SOIL CONDITIONER MIX. INSTALL DRIP IRRIGATION TO EACH PLANT

75mm ORGANIC MULCH, DISH AT PLANT STEM

ADD NATIVE PLANT FERTILISER PELLET

SPREAD 100 SITE TOPSOIL AND 50MM ORGANIC SOIL CONDITIONER AND CULTIVATE TO A FINE TILTH

1 **CULTIVATED PLANTING PREPARATION**

SECTION SCALE 1:20

LEGEND

- Existing retained vegetation - Woodland
- Proposed Cropping areas
- Proposed screen planting- local native species
- Trees to be removed
- Trees to be retained
- Existing dwellings
- Existing outbuildings
- Site Boundary

0 10 20 30 40 50 M

N

issue

Lindy Lean
LANDSCAPE ARCHITECT
AAILA Registered Landscape Architect #0423
HLS Pty Ltd PO Box 313 Ashfield NSW
phone 02 9797 9366

Proposed Dam and Market Gardens Development
140 Ashwood Road Wilton NSW (Lot 542 DP 559948)
FOR **Yan Zhen Huang and Associates**

Landscape Plan

L01

1:500 @A1 15 October 2019 status For DA issue A

Bulfin/ wilton - Ashwood Rd Landscape.vwx18 print date 15 Oct 2019